




SITE AERIAL VIEW



Project Analysis	
Project no: BC0223	Dated: Jun 17, 2023
This project date is preliminary at this stage of the project. Exact scope, zoning, uses and size only be determined upon the city hall approval. Design review, civil and code issues, site and tree survey may change from the written below. Therefore the client should not base any purchase, building cost and any other decision on this document.	
Municipal Address:	1901 Northfield road, Nanaimo BC
Legal Address:	LOT A, SECTION 17, RANGE 8, MOUNTAIN DISTRICT, PLAN 47335
Zoning:	R1
Proposed Zoning:	R8
Permitted Uses:	Medium Density Residential
Site Area:	2071.92 m ²
Net site area:	1909.4 m ²
Lot Coverage:	40% - provided 40%
Unit Density:	
Residential net Areas	27,289 sqft
Common Area	
Indoor amenity area	900 sqft
Gross floor area	sqft (sqmts)
Maximum permitted FAR:	1.6 or 1.60 x 1909.4 = 3,055 sq.mts - Provided FAR = 1.5
FAR Exclusions	
Bulk storage	
Amenity (covered outdoor)	
Amenity (LS deck and roof deck)	
Roof deck access	
Balcony	
Deck	
Garbage room	162 sqft
Parkade and service area	
Total exclusions:	
Amenity:	
2.3 sq.mts per dwelling unit	
Indoor amenity area	
Covered outdoor amenity area	
Total dwelling units	35
2 bed room units	11
1 bed room units	24
5% adaptable units required	
SETBACKS	
Front yard:	6m
Front yard provided:	6m
Back Yard:	10.5m
Rear Yard provided:	10.5
Side yard:	3m
Side yard provided:	3m
Flanking Side yard	6m
Flanking Side yard provided:	
Average Grade:	
South	
East	
North	
West	
Building height	
Height of Principal Building - Flat Roof1 (c than 4:12 pitch)	14m Up to 4-stories
Height of Principal Building - Sloped Roof1 (2:4:12 pitch)	14m
Parking Requirements:	
Loading stalls required:	
Off street parking	
RMB HIGH DENSITY RESIDENTIAL	
1-BED ROOM = 1.7/UNIT	11 x 1.76 = 25.46
2-BED ROOM = 1.3/UNIT	11 x 1.62 = 17.82
VISITOR PARKING = 1/22 stalls	35/22 or 1.59 ~ 2 stalls
Total parking required:	46 stalls
CITY CENTRE 5% REDUCTION CONSIDERED	
TOTAL PARKING PROVIDED	46
Bike Parking	
Bike parking provided	
Short term 0.1/unit	0.1/35 = 3.5
Long term 0.5/unit	0.5/35 = 17.5
Total Bike parking	21
(PLEASE NOTE THE GEOTECHNICAL ELEVATIONS CONTRACTOR TO CONFIRMED AS PER THE CIVIL DRAWINGS)	



1 SITE PLAN
DP101 1" = 10'-0"

Edmonton 780.425.2752 (p)
Winnipeg 204.515.6699 (p)
Vancouver (Downtown) 604.678.0518 (p)
West Vancouver 604.754.9977 (p)

Kumar Architecture Ltd.
www.kumararchitecture.com
admin@kumararchitecture.com
Excellence, Innovation and Holistic Designs

Rev.			mm-dd-yy	Revision /Drawing Issue	Drawn by	TD
1	2023-09-23	ISSUE FOR DP				

CONSULTANT

PERMIT STAMP

SEAL

THIS DRAWING, AS AN INSTRUMENT OF SERVICE IS THE PROPERTY OF KUMAR ARCHITECTURE LTD. THE COPYRIGHT IN THE SAME BEING RESERVED TO THEM. NO REPRODUCTION IS ALLOWED WITHOUT THE PERMISSION OF KUMAR ARCHITECTURE AND WHEN IT IS MADE MUST BEAR ITS NAME. THIS DRAWING IS NOT TO BE SCALED. THE CONTRACTOR IS TO VERIFY THE DIMENSIONS AND DATA NOTED HEREIN WITH THE CONDITIONS ON SITE AND IS RESPONSIBLE FOR REPORTING ANY DISCREPANCY TO KUMAR ARCHITECTURE LTD FOR ADJUSTMENT.

PROJECT
NORTHFIELD MULTIFAMILY
1901 NORTHFIELD ROAD NANAIMO BC

DRAWING TITLE
SITE PLAN

Project number BC0223	Date Scale As indicated	Issue Date As indicated
Drawn by Author	Checked by Checker	REVISION 1

RECEIVED
DP1332
2024-FEB-01
Current Planning